

BIIL OF QUANTITIES FOR THE PROPOSED CLASSROOM CONSTRUCTION FOR
CHILDREN GARDEN HOME NAIROBI.

NO	DESCRIPTION	UNIT	QUANTITY	UNIT RATE	AMOUNT
	<u>ELEMENT 01 STAIRCASE.</u>				
A	Excavate column pit for foundation column not exceeding 1.5m deep	CM	21.78	450.00	9,801.00
B	Vibrated reinforced concrete of class 20 mixed in ratio of 1:2:4 to column bases.	CM	1.5	12,260.00	18,390.00
C	Vibrated reinforced concrete mixed in ratio of 1:2:4 to staircase columns and beams.	CM	25	12,260.00	306,500.00
D	Formwork to soffit of the stairecase flight, landing edges and beam surfaces.	SM	71	700.00	49,700.00
E	Formwork to edges of the staircase risers	LM	40.4	130.00	5,252.00
F	Reinforcement to foundation bases, columns and stairecase of D12 main bars and D8 stirups	KG	891.54	150.00	133,731.00
G	Vibrated reinforced concrete of class 20 mixed in ratio of 1:2:4 to staircase.	CM	4	12,260.00	49,040.00
H	Balustrades of 1m high comprising of standard newels @ 2m c/c, balusters @ 100mm c/c and handrail to staircase and landing with and including painting to staircase.	LM	12	4,500.00	54,000.00
I	Balustrades of 1m high comprising of standard newels @ 2m c/c, balusters @ 100mm c/c and handrail to balcony with and including painting to balcony	LM	13.6	4,500.00	61,200.00
J	Binding wire	NO	2	3,600.00	7,200.00
TOTAL CARRIED TO SUMMERY					694,814.00

BIIL OF QUANTITIES FOR THE PROPOSED CLASSROOM CONSTRUCTION FOR
CHILDREN GARDEN HOME NAIROBI.

NO	DESCRIPTION	UNIT		UNIT RATE	AMOUNT
	<u>ELEMENT 02 SUPERSTRUCTURE WORK.</u>				
A	Superstructure walling bedded with cement sand mortar and whoop iron after every alternae course (wall thickness 200mm) to balcony, staircase and classrooms.	SM	200	1,700.00	340,000.00
B	Window mesuring 2500x1500mm with standard window pane and ventilations including iron mongeries, glazing and painting.	NO	2	21,650.00	43,300.00
C	Plain flush door measuring 900x2100 including iron mongery and painting.	NO	2	17,800.00	35,600.00
D	Vibrated reinforced concrete (300x200mm) of ratio 1:2:4 to superstructure columns and beams	CM	5.5	12,260.00	67,430.00
E	Sawn softwood Formwork to the surface of the beams and columns	SM	65	700.00	45,500.00
F	Reinforcement to balcony columns amd beams with stirups spaced @ 200c/c	KG	500.15	150.00	75,022.50
G	Flat roofing timber joists of trusses @ 1.2m c/c				
	100x50mm	LM	165	650.00	107,250.00
	75x50mm	LM	165	500.00	82,500.00
H	Box profile roof covering guage 30	SM	114	1,050.00	119,700.00
I	Scaffolding of not less then 1.5m wide and 5m long	LM	39	1,100.00	42,900.00
J	200x25mm fascia board with and including two coats of painting externally	LM	39	700.00	27,300.00
K	Whoop iron	NO	2	3,800.00	7,600.00
	TOTAL CARRIED TO SUMMERY				994,102.50

BIIL OF QUANTITIES FOR THE PROPOSED CLASSROOM CONSTRUCTION FOR
CHILDREN GARDEN HOME NAIROBI.

NO	DESCRIPTION	UNIT		UNIT RATE	AMOUNT
	<u>ELEMENT 03 FINISHES.</u>				
A	Plastering with cement sand mortar in ratio of 1:3 to internal walls, columns and beams.	SM	197	400.00	78,800.00
B	Prepare and apply three coats of paint to internal walls, columns and beams	SM	197	360.00	70,920.00
C	Floor screading of cement sand mortar (1:3) with cement paste finish to classrooms, balcony.	SM	89.56	450.00	40,302.00
D	External wall finishing (pointed keying)	SM	118	380.00	44,840.00
E	Plastering with cement sand mortar in ratio of 1:3 to staircase soffit, treads, risers, and landing.	SM	40.2	360.00	14,472.00
F	Ceiling joists @ 600mm c/c				
	100x50mm joists	LM	140	500.00	70,000.00
	100x75mm joists	LM	140	650.00	91,000.00
G	12mm gypsum boards as ceiling boards	SM	109	2,200.00	239,800.00
H	Prepare and apply three coats of paint to ceiling	SM	109	360.00	39,240.00
I	Halfrounded cornice	LM	43.4	450.00	19,530.00
	TOTAL CARRIED TO SUMMERY				708,904.00

BIIL OF QUANTITIES FOR THE PROPOSED CLASSROOM CONSTRUCTION FOR
CHILDREN GARDEN HOME NAIROBI.

NO	ELEMENT	DESCRIPTION	AMOUNT
	<u>SUMMERY</u>		
1	ELEMENT 01	STAIRCASE	694,814.00
2	ELEMENT 02	SUPERSTRUCTURE WORKS	994,102.50
3	ELEMENT 03	FINISHES	708,904.00
	SUBTOTAL		2,397,820.50
4	MISCELLANEOUS	ADD 10%	239,782.05
	TOTAL		2,637,602.55
	GRAND TOTAL		2,637,602.55