

ITEM	DESCRIPTION	UNIT	QUAN	RATE (KSHS)	AMOUNT (KSHS)
	PROPOSED RENOVATION FOR CHILDREN GARDEN HOME,NAIROBI ELEMENT NO.1				
	WALL FINISHES				
	<u>Plaster;12mm thick 2No coatworks,9mm first coat of cement sand(1:3);3mm second coat of cement and lime putty(1:10); steel trowelled to concrete or blockwork base generally to:</u>				
A	Wall and beam internally	SM	92	800.00	73,600.00
B	Plastered surfaces: walls,beams ,columns	SM	92	500.00	46,000.00
C	Prepare and apply three coats of first quality silk vinyl paint to; Plastered surfaces;walls,beams and columns	SM	60	400.00	24,000.00
D	<u>Plaster;12mm thick render to external surfaces steel trowelled to receive paint;</u> Walls,beams ,columns; Externally	SM	60	600.00	36,000.00
	Painting and decorations				
	<u>Prepare and apply three coats of first quality silk vinyl paint to;</u>				
E	Plastered surfaces;walls ,beams and columns	SM	60	800.00	48,000.00
	KITCHEN WALLS				
	<u>Screed ;cement and sand(1:3)</u>				
F	200mm thick one coat backings;wood floated to receive ceramic wall tiles(m/s) to concrete base ,to worktop level,internal	SM	9	600.00	5,400.00
	<u>Approved ;local; ceramic wall tiles to regular or other approved pattern;bedding and jointing in cement sand(1:4) mortar; grouting with matching cement</u>				
G	200mmx100mm marble effect tiles backspash in flemish bond pattern	SM	9	2,000.00	18,000.00
	<u>Prepare and apply three coats of first quality of black bitumastic paint to: -</u>				
H	Chalkboard to Education section	SM	8	300.00	2,400.00
	<u>CLAY BLOCK FACADES</u>				
	Supply and fix 200mmx200mmx60mm thick Teracotta clay block facade to ;				
I	Entrance	SM	3	2,500.00	7,500.00
J	External wall	SM	31	2,500.00	77,500.00
	TOTAL WALL FINISHES CARRIED TO SUMMARY			KSHS	338,400.00

ITEM	DESCRIPTION	UNIT	QUAN	RATE (KSHS)	AMOUNT (KSHS)
	ELEMENT NO. 2				
	<u>CEILING AND FLOOR FINISHES</u>				
	<u>CEILING FINISHES TO EDUCATION & SOCIAL TRAINING SECTION</u>				
A	12mm thick Gypsum ceiling matte while RAL 9010	SM	40	4,500.00	180,000.00
	<u>CORRIDOR CEILING FINISH</u>				
B	25mm thick celotex softboard ceiling board complete with surface mounted ceiling lights	SM	24	2,500.00	60,000.00
	<u>FLOOR FINISH</u>				
B	25mm thick cement sand screed steel towelled hard and finished smooth to entire floor	SM	64	600.00	38,400.00
	<u>PARTITION</u>				
C	8mm thick Polycarbonate panels separating education area to social training area	SM	6	20,000.00	120,000.00
	TOTAL FLOOR AND CEILING FINISH CARRIED TO SUMMARY			KSHS	398,400.00

ITEM	DESCRIPTION	UNIT	QUAN	RATE (KSHS)	AMOUNT (KSHS)
	ELEMENT NO.3				
	<u>WINDOWS AND DOORS</u>				
	<u>Anadised powder coated aluminium casement window 45mm thick complete with and including ,air vent,sealant, sound proof rubber seal and necessary iron mongery</u>				
A	With 6mm thick clear sheet glazing	SM	6	8,000.00	48,000.00
	DOORS				
B	Supply and fix 8mm sheet poycarbonate doors with and including the necessaryu iron mongery to architect's approval	SM	11	20,000.00	220,000.00
	Mild steel casement doors; 50x50x3mm thick frame plugged to block work with 100mm long fishtailed 25x25x2mm thick angle section frames at 300mm centres both sides, angles cut, mitred and welded; panels in filled with 4mm thick glazing at top panel and 16 gauge black sheet panel at both middle and bottom panels as detailed in the drawing, one coat manufacturer's primer, complete with all necessary ironmongery; all welding ground to smooth finish				
C	Single door with equal leaves 900 x 2400mm high including 3 pairs 10mm long purpose made hinges; 2 no 400mm tower bolt; and 1no. 300mm D handle	NO	1	10,000.00	10,000.00
	TOTAL FOR WINDOWS AND DOORS CARRIED TO SUMMARY			KSHS	278,000.00

ITEM	DESCRIPTION	UNIT	QUAN	RATE (KSHS)	AMOUNT (KSHS)
	ELEMENT NO.4				
	KITCHEN APPLIANCES				
A	Gas cooker ,4 burner as Anets GPC14' OR equivalent;made of stainless steel pot,front and sides complete with grill and adjustable continous water fill and electronic ignition.	NO	1	60,000.00	60,000.00
B	Fridge as Ramtons-RD24WR or equivalent, volume 0.31m3 double door, mechanically controlled with adjustable thermostat	NO	1	120,000.00	120,000.00
C	Dishwasher as Whirlpool or equivalent;capacity 500 plates per hour,monochromatic stainless finish with stainless steel tub and sensor cycle 48dBA	NO	1	85,000.00	85,000.00
D	Supply and install ,test and commission a kitchen hood as Larkin model E O size 3000mmx 1200mm complete with extraction fan ans associated ducting including aluminium baffle filter,collars ,hanging brackets ,stainless grease trough and cup	NO	1	30,000.00	30,000.00
E	Lay gas piping dia 12.7mm complete with accessories from enclosed gas cylinder beside the gas cooker	NO	1	10,000.00	10,000.00
	CABINETS				
F	Supply and fix low storage cabinets at the education csection 2500mmx 900mm high ;with double openable shelves;made of 18mm thick UV PVC melanine laminated MDF ;with pianno hinges and door handles	SUM	1	80,000.00	80,000.00
G	Supply and fix low level (900mm high)storage cabinet at the kitchen area with lockable drawers ,pull out baskets and ceramic worktop ;together with suspended 12mm thick particle board shelving in melanine white finish around the kitchen hood	SUM	1	200,000.00	200,000.00
TOTAL FOR KITCHEN APPLIANCES & CABINETS CARRIED TO SUMMARY				KSHS	585,000.00

5

ITEM	DESCRIPTION	UNIT	QUAN	RATE (KSHS)	AMOUNT (KSHS)
	SUMMARY				
	TOTAL BROUGHT DOWN FROM PAGE 1				338,400.00
	TOTAL BROUGHT DOWN FROM PAGE 2				398,400.00
	TOTAL BROUGHT DOWN FROM PAGE 3				278,000.00
	TOTAL BROUGHT DOWN FROM PAGE 4				585,000.00
	TOTAL FOR BUILDERS WORK CARRIED TO SUMMARY			KSHS	1,599,800.00

ITEM	DESCRIPTION				AMOUNT
	PROPOSED RENOVATION FOR CHILDREN GARDEN HOME,NAIROBI				
	SUMMARY				
	ELEMENT				
1	PRELIMINARIES				200,000.00
2	BUILDERS WORK				1,599,800.00
	SUB-TOTAL NO.1				1,799,800.00
	ADD 16% V.A.T				287,968.00
	SUB-TOTAL NO.2				2,087,768.00
	P.C & PROVISIONAL SUMS				500,000.00
	TOTAL CARRIED TO FORM OF TENDER			Kshs.	2,587,768.00
<u>EMPLOYER</u> NAME..... SIGNATURE..... ADDRESS..... DATE.....				<u>CONTRACTOR</u> NAME..... SIGNATURE..... ADDRESS..... DATE.....	